

---

## NOTICE TO CONTRACTORS

---

STATE OF CALIFORNIA  
THE RESOURCES AGENCY  
DEPARTMENT OF WATER RESOURCES

### HIGHLIGHTED CHANGE FROM ADDENDUM NO. 2

Sealed bids for ROOFING REPLACEMENT, OROVILLE FIELD DIVISION, STATE WATER FACILITIES, BUTTE AND PLUMAS COUNTIES, CALIFORNIA, SPECIFICATION NO. 05-09, CONTRACT NO. C51303, will be received by the Department of Water Resources, 1416 Ninth Street, Room 418, Sacramento, California 95814, not later than **2:00 P.M. on WEDNESDAY, JUNE 29, 2005**, at which time they will be publicly opened and read at an announced location in the vicinity of such office.

Bid forms for this work are included in a separate booklet titled BID FORM. Bids will be considered only if submitted for all the work required for the above project. The work is defined in Section 01110 – Summary of Work, and includes but is not limited to the following principal features:

1. Replacement work for Oroville O&M Center Planner Scheduler Building at location shown. This work includes: a. Removal of existing roof to the existing metal deck as shown, b. Installation of new roofing system as shown, which includes: 1) Removal and reinstallation of existing equipment, 2) Tapered roofing installation, 3) Torch applied roof base, 4) Granular SBS modified bitumen cap sheet, 5) Modification of roof skylight and equipment curbs, 6) New equipment rails, 7) Modification of Heating, Ventilating and Air Conditioning (HVAC) equipment duct, 8) Relocation of existing gas pipes at Air Conditioning (A/C) units. Replacement of any rusty gas pipes/fittings at A/C units as needed, 9) Replacement of any existing deteriorated flexible isolation connections at A/C units, 10) Replacement of A/C drain lines with missing traps, 11) Remove two existing unused exhaust fans located next to existing skylights, 12) Sheet metal work, 13) Sealants, 14) Covering existing roof drains, 15) New walk pads, 16) New gutters and downspouts, 17) Replace existing roof vent with new roof vent as shown, and c. Painting.

2. Roof replacement work for Oroville O&M Center Mobile Equipment Building at location shown. This work includes: a. Removal of existing roof to the existing metal deck as shown, b. Installation of new roofing system as shown, which includes: 1) Removal and reinstallation of existing equipment, 2) Tapered roofing installation, 3) Torch applied roof base, 4) Granular SBS modified bitumen cap sheet, 5) Modification of roof skylight and equipment curbs, 6) Replacement of existing damaged turbine ventilators, 7) Replacement of existing skylight domes, 8) Replacement of existing exhaust fan above bathroom, 9) Replacement of all existing cement fascia and soffit boards, including some damaged plywood and nailer, 10) Sheet metal work, 11) Sealants, 12) Covering existing roof drains, 13) New gutters and downspouts, and c. Painting.

3. Roof replacement work for Feather River Fish Hatchery, Thermalito Facility at location shown. This work includes: a. Removal of existing roof to the existing metal deck as shown, b. Installation of new roofing system as shown, which includes: 1) Removal and reinstallation of existing equipment, 2) Tapered roofing installation, 3) Torch applied roof base, 4) Granular SBS modified bitumen cap sheet, 5) Modification of roof skylight and equipment curbs, 6) Replacement of existing damaged turbine ventilators, 7) Replacement of existing skylight domes, 8) Replacement of existing exhaust fan above bathroom, 9) Replacement of all existing cement fascia and soffit boards, including some damaged plywood and nailer, 10) Sheet metal work, 11) Sealants, 12) Covering existing roof drains, 13) New gutters and downspouts, and c. Painting.

4. Roof replacement work for Beckwourth Subcenter at location shown. This work includes:  
a. Removal of existing roof to the existing metal deck as shown, b. Removal and disposal of existing rooftop solar panel system including panels, supporting platform, and related ductwork and electrical wiring as shown, c. Removal and disposal of existing heat storage unit associated with rooftop solar panel system, d. Removal of existing gutters and downspouts, e. New roofing system as shown, which includes: 1) Removal and reinstallation of existing equipment, 2) Tapered roofing, 3) Torch applied roof base, 4) Granular SBS modified bitumen cap sheet, 5) Modification of roof equipment curbs, 6) Sheet metal work, 7) Sealants, 8) New roof gutters and downspouts, 9) New cement siding, and f. Painting.

Forms of bid and contract, drawings and specifications for the project may be obtained only at the Department of Water Resources, 1416 Ninth Street, Room 418, Sacramento, California, between the hours of 7:30 a.m.-12:00 noon and 12:30-4:00 p.m. or by mail upon written request to the Department of Water Resources, P. O. Box 942836, Sacramento, California 94236-0001, Attention: Jim Veres, Spec. No. 05-09, Telephone (916) 653-4867, Fax (916) 653-6166, or by e-mail at [doe\\_specs@water.ca.gov](mailto:doe_specs@water.ca.gov). Drawings and specifications may be seen at the above location or at the office of the Department at 3121 East Avenue I, Lancaster, California.

The Department encourages bidders to explore certification as a Small Business and/or Disabled Veteran Business Enterprise and to utilize certified Small Business and Disabled Veteran Business Enterprises during the contract term.

Contractor's license classification required for this work: C-39 or B w/C-39 Subcontractor.

LESTER A. SNOW  
Director of Water Resources

Dated: May 20, 2005  
(Advertisement)