

## NOTICE TO CONTRACTORS

STATE OF CALIFORNIA  
THE RESOURCES AGENCY  
DEPARTMENT OF WATER RESOURCES

Sealed bids for PENSTOCK BYPASS LINE CONNECTION, MOJAVE SIPHON POWERPLANT, STATE WATER FACILITIES, CALIFORNIA AQUEDUCT, SOUTHERN FIELD DIVISION, SAN BERNARDINO COUNTY, CALIFORNIA, SPECIFICATION NO. 07-09, CONTRACT NO. C51348, will be received by the Department of Water Resources at the Lancaster Project Headquarters, 121 West Carriage Lane, Suite 101, Lancaster, California 93534, not later than **11:00 A.M. on THURSDAY, JUNE 21, 2007**, at which time they will be publicly opened and read at an announced location in the vicinity of such office. Lancaster Project Headquarters is located on a new street just north of the NW corner of Division Street and East Avenue K.

Bid forms for this work are included in a separate booklet titled BID FORM. Bids will be considered only if submitted for all the work required for the above project. The work is defined in Section 01110 – Summary of Work, and includes but is not limited to the following principal features:

1. Furnish and install one 120 inch diameter and approximately 60 foot long steel pipe, fabricated with 80 degree bend, to be placed for connection from the existing tee on Barrel Number 3 to the existing abandoned Prestressed Concrete Cylinder Pipe (PCCP) as shown. This work includes: a. Dewatering, b. Demolition and removal of existing sections of PCCP, c. Fabricated steel pipe, fittings and connection, d. Fabricate and install 12 precast reinforced concrete stoplogs at the Inlet Structure, Check 66, e. Earthwork for bypass line and structures, f. Clearing and grubbing, g. Encasement of exposed pipe sections, h. Reinforced concrete structures with a manhole, i. Installation of precast structure with a hatch for manhole, j. Modification of the existing 12 inch bypass inside the existing valve vault and install drainage line including earthwork, valves and pipe supports, and connecting to the existing sump pump, k. Removal of existing 144 inch internal steel bulkhead, l. Mechanical work, including testing existing HPU and 120 inch bypass valve, m. Electrical work, n. Seeding, and o. Coatings.

Forms of bid and contract, drawings and specifications for the project may be obtained only at the Department of Water Resources, 1416 Ninth Street, Room 418, Sacramento, California, between the hours of 7:30 a.m.-12:00 noon and 12:30-4:00 p.m. or by mail upon written request to the Department of Water Resources, P. O. Box 942836, Sacramento, California 94236-0001, Attention: Jim Veres, Spec. No. 07-09, Telephone (916) 653-4867, Fax (916) 653-6166, or by e-mail at [doe\\_specs@water.ca.gov](mailto:doe_specs@water.ca.gov). Drawings and specifications may be seen at the above location or at the office of the Department at Lancaster Project Headquarters, 121 West Carriage Lane, Suite 101, Lancaster, California, 93534.

The Department encourages bidders to explore certification as a Small Business and/or Disabled Veteran Business Enterprise and to utilize certified Small Business and Disabled Veteran Business Enterprises during the contract term.

Contractor's license classification required for this work:   A   .

All bidders shall be prequalified by the Department. Bid documents will be furnished only to prequalified bidders who meet the requirements of the State Contract Act and Document 00040 – Prequalification.

LESTER A. SNOW  
Director of Water Resources

Dated:   May 11, 2007    
(Advertisement)