
NOTICE TO CONTRACTORS

STATE OF CALIFORNIA
THE RESOURCES AGENCY
DEPARTMENT OF WATER RESOURCES

Sealed bids for ROOFING REPLACEMENT AND RECOATING, OSO PUMPING PLANT, PEARBLOSSOM PUMPING PLANT, PEARBLOSSOM O&M SUBCENTER BUILDINGS, AND QUAIL LAKE OUTLET BUILDING, STATE WATER FACILITIES, CALIFORNIA AQUEDUCT, SOUTHERN FIELD DIVISION, LOS ANGELES COUNTY, CALIFORNIA, SPECIFICATION NO. 08-02, CONTRACT NO. C51366, will be received by the Department of Water Resources, at the Lancaster Project Headquarters, 121 West Carriage Lane, Suite 101, Lancaster, California 93534, not later than **11:00 A.M., THURSDAY, MARCH 20, 2008**. Lancaster Project Headquarters is located on a new street just north of the NW corner of Division Street and East Avenue K, at which time they will be publicly opened and read at an announced location in the vicinity of such office.

Bid forms for this work are included in a separate booklet titled BID FORM. Bids will be considered only if submitted for all the work required for the above project. The work is defined in Section 01110 – Summary of Work, and includes but is not limited to the following principal features:

1. Removing and replacing a total of approximately 49,000 square feet of roofing at five structures; Oso Pumping Plant, Quail Lake Outlet control building, and the Civil Maintenance building, Warehouse, and Weld Shop at the Pearblossom Subcenter. Reroofing work includes: removing and disposing of existing roofing, roof sheathing, and roof insulation; removing skylights at some structures; providing roof insulation, SBS modified bitumen roofing system, reflective roof coating, curb modifications, sheet metal work, and sealants; and providing skylights, expansion joints, gutters, and downspouts at some structures.
2. Recoating approximately 25,400 square feet of the Pearblossom Pumping Plant roof (approximately 85% of the total roof area). Recoating work includes preparing the surface, applying a polyester reinforced elastomeric roof coating system with white acrylic reflective roof coating, and inspection and testing of the coating.
3. Covering approximately 4,900 square feet of the Pearblossom Pumping Plant roof. Covering work includes preparing the surface, installing cover board over existing roofing, SBS modified bitumen roofing system, reflective roof coating, sheet metal work, sealants, expansion joint cover, curb modifications, and painting gutters, downspouts and sheet metal work.

Forms of bid and contract, drawings and specifications for the project may be obtained only at the Department of Water Resources, 1416 Ninth Street, Room 418, Sacramento, California, between the hours of 7:30 a.m.-12:00 noon and 12:30-4:00 p.m. or by mail upon written request to the Department of Water Resources, P. O. Box 942836, Sacramento, California 94236-0001, Attention: Jim Veres, Spec. No. 08-02, Telephone (916) 653-4867, Fax (916) 653-6166, or by e-mail at doe_specs@water.ca.gov. Drawings and specifications may be seen at the above location or at the office of the Department at Lancaster Project Headquarters, 121 West Carriage Lane, Suite 101, Lancaster, California, 93534.

The Department encourages bidders to explore certification as a Small Business and/or Disabled Veteran Business Enterprise and to utilize certified Small Business and Disabled Veteran Business Enterprises during the contract term.

Contractor's license classification required for this work: C-39 or B w/C-39 Subcontractor .

All bidders shall be prequalified by the Department. Bid documents will be furnished only to prequalified bidders who meet the requirements of the State Contract Act and Document 00040 – Prequalification.

LESTER A. SNOW
Director of Water Resources

Dated: February 15, 2008
(Advertisement)