
NOTICE TO CONTRACTORS

STATE OF CALIFORNIA
THE RESOURCES AGENCY
DEPARTMENT OF WATER RESOURCES

Sealed bids for EROSION REPAIR, WATERLINE REPLACEMENT AND BUILDING MODIFICATIONS, VISTA DEL LAGO VISITORS CENTER, STATE WATER FACILITIES, CALIFORNIA AQUEDUCT, WEST BRANCH, SOUTHERN FIELD DIVISION, LOS ANGELES COUNTY, CALIFORNIA, SPECIFICATION NO. 08-04, CONTRACT NO. C51368, will be received by the Department of Water Resources at the Lancaster Project Headquarters, 121 West Carriage Lane, Suite 101, Lancaster, California 93534, not later than **11:00 A.M. on THURSDAY, JUNE 5, 2008**, at which time they will be publicly opened and read at an announced location in the vicinity of such office. Lancaster Project Headquarters is located on a new street just north of the NW corner of Division Street and East Avenue K.

Bid forms for this work are included in a separate booklet titled BID FORM. Bids will be considered only if submitted for all the work required for the above project. The work is defined in Section 01110 – Summary of Work, and includes but is not limited to the following principal features:

1. Sitework related to the landslide repair at Vista Del Lago Visitors Center, including: a. Clear vegetation and cut temporary access road from Vista Del Lago Road to the slide area, b. Remove loose soil and cut benches in the existing landslide area, c. Import and place backfill material and geogrid material in layers along the horizontal surface and compact, d. Install new subsurface drainage, e. Backfill temporary access road to pre-construction condition, 2. Sitework related to water intake system, including: a. Install two new submersible supply water pumps and new pump platforms, b. Excavate trench and install new water supply pipeline, valves and electrical power cables from new supply water pumps to water treatment building following new alignment, c. Backfill and compact trench, d. Install aggregate base and asphalt concrete patch at trench along roadway, e. Remove the two existing supply water pumps, pipelines and power cables. Southern Field Division will retain possession of the two pumps, 3. Vista Del Lago Visitors Center building modifications and associated subsurface and building drainage systems, including: a. Install new gutters and downspouts and PVC storm water drainage pipe, b. Install new subsurface drainage, c. Remove existing exterior insulation plaster finish at fascia beam, unit pavers and concrete at entrance, d. Install structural modifications to roof and addition of furred columns at building entrance, including steel pipe columns, concrete pads and tile pavers, e. Install additional aluminum storefronts, and f. Inspect, clean, replace wood members as shown, and paint the wood pergola.

Forms of bid and contract, drawings and specifications for the project may be obtained only at the Department of Water Resources, 1416 Ninth Street, Room 418, Sacramento, California, between the hours of 7:30 a.m.-12:00 noon and 12:30-4:00 p.m. or by mail upon written request to the Department of Water Resources, P. O. Box 942836, Sacramento, California 94236-0001, Attention: Jim Veres, Spec. No. 08-04, Telephone (916) 653-4867, Fax (916) 653-6166, or by e-mail at doe_specs@water.ca.gov. Drawings and specifications may be seen at the above location or at the office of the Department at Lancaster Project Headquarters, 121 West Carriage Lane, Suite 101, Lancaster, California, 93534.

The Department encourages bidders to explore certification as a Small Business and/or Disabled Veteran Business Enterprise and to utilize certified Small Business and Disabled Veteran Business Enterprises during the contract term.

Contractor's license classification required for this work: A .

All bidders shall be prequalified by the Department. Bid documents will be furnished only to prequalified bidders who meet the requirements of the State Contract Act and Document 00040 – Prequalification.

LESTER A. SNOW
Director of Water Resources

Dated: May 2, 2008
(Advertisement)