


# Budiselich Flashboard Dam Fish Passage Improvement Project

Randy Beckwith, Senior Engineer

CA Department of Water Resources

Fish Passage Improvement Program



Salmonid Restoration Federation

Fish Passage and Protection Workshop

April 4, 2012

# Fish Passage Improvement Program

- Formed in 1999
- Staffed with Environmental Scientists and Engineers
- Funded mainly through the Ecosystem Restoration Program (CalFed/DFG)
- Provides in-kind services on passage projects, mainly in the Central Valley to support ERP objectives

# Presentation Outline

- Colleagues, Partners, and Roles
- Background
- Fish Passage Issues at Budiselich
- Design
- Construction
- Monitoring

# Presentation Outline

- **Colleagues, Partners, and Roles**
- Background
- Fish Passage Issues at Budiselich
- Design
- Construction
- Monitoring

# CA Department of Water Resources

## Fish Passage Improvement Program

- Trevor Greene
- Colin Hanley
- Roger Padilla
- James Newcomb
- Leslie Pierce

## Division of Engineering

- Joe Royer
- Will Hicks
- Chris Erickson
- Arnie Sanchez
- Jeannie Kuttel

# Partners

## Stockton East Water District

- **John Green**
- Jacob Bejarano
- Kevin Kauffman
- Andres Lozano
- Tom Bergin
- The construction crew

## CA Dept. of Fish and Game

- **George Heise**

## USFWS

- **Donnie Ratcliff**
- Ramon Martin
- David Hu (now with USFS)

## Fishery Foundation

- Kari Burr
- Trevor Kennedy

# Roles

## DWR Fish Passage Improvement Program

- Topographic Surveying
- Design
- Hydraulic Modeling
- Hydraulic Monitoring

## USFWS

- Funding
- Calaveras Fish Group Coordination

## Stockton East Water District

- Funding
- Coordination
- Permitting
- Construction

## DFG

- Funding
- Technical Engineering Assistance


# Presentation Outline


- Colleagues, Partners, and Roles
- **Background**
- Fish Passage Issues at Budiselich
- Design
- Construction
- Monitoring

# Target Species

- Central Valley Steelhead (*Oncorhynchus mykiss*)
- Fall-run Chinook salmon (*Oncorhynchus tshawytscha*)

# Lower Calaveras River





**Calaveras River just below New Hogan Dam –  
Looking Downstream**

# Old Calaveras River channel east of Stockton

Downstream towards  
Stockton




# Mormon Slough



A photograph of the Stockton Diverting Canal. The canal is a narrow, shallow channel of water flowing through a dirt path. The path is flanked by green grass and some debris, including a tire and some plastic. In the background, there are trees and a few buildings. The sky is overcast.

# Stockton Diverting Canal



Assessments


**Calaveras River Fish Migration Barriers Assessment Report**

RESOURCE RESTORATION DIVISION OF PLANNING & LOCAL ASSISTANCE DEPARTMENT OF WATER RESOURCES

SEPTEMBER 2007

**Worst Fish Passage Barriers (not in order of ranking)**

- 1 Calaveras Headworks
- 2 Clements Flashboard Dam
- 3 Cherryland Flashboard Dam
- 4 Gotelli Low Flow Road Crossing
- 5 Central California Railroad Crossing
- 6 Budiselich Flashboard Dam
- 7 Caprini Low Flow Road Crossing
- 8 Hosie Low Flow Road Crossing



**Budiselich Flashboard Dam – Calaveras Fish Group’s No. 1 Priority**




# Presentation Outline

- Colleagues, Partners, and Roles
- Background
- **Fish Passage Issues at Budiselich**
- Design
- Construction
- Monitoring

# Budiselich Flashboard Dam Foundation

- 100 feet between the abutments and 12 feet wide
- Unknown thickness as we do not have as-built drawings




# Fish Passage Issues

**Steep slope downstream of foundation (7%), much of it over riprap**

**Shallow flow over foundation – does not meet 1' depth criterion until 190 cfs**

**No well-defined passage channel downstream of the foundation**

**Flow**  
←



**October 24, 2001**



**Steep slope and riprap**

**February 28, 2006 – Flow Magnitude Unknown**



**February 4, 2004 - 185 cfs**



February 19, 2004 - 267 cfs



# Presentation Outline


- Colleagues, Partners, and Roles
- Background
- Fish Passage Issues at Budiselich
- **Design**
- Construction
- Monitoring

January 2009

Topographic Survey



# Longitudinal Profile




# Design Alternatives

3. Roughened channel to lessen slope and to backwater foundation

2. Partial-depth notch with roughened channel to lessen slope

1. Dam removal



# Preferred Alternative

**Alternative 3 - No alteration to dam and construction of a roughened channel downstream**

**Because:**

- **SEWD still uses the dam**
- **Design team thought construction would be simpler**
- **The dam is of unknown**
  - **Thickness**
  - **Stability**
  - **Integrity**

# Roughened Channel Design Goal

- Greatly improve fish passage by creating a nature-like passage channel that:
  - Reduces the slope downstream
  - Provides adequate depths
  - Removes riprap
  - Provides multiple passage paths
  - Is stable at all flows




# Design Guidance and Criteria

- **Used DFG's Fish Passage Design and Implementation Manual**
- **Used hydraulic design method, which uses fish swimming abilities for guidance**
- **Designed for adult anadromous salmonids**
- **Met DFG and NMFS criteria and guidelines**

# Initial Roughened Channel Design

- Step-pool, boulder weir design
- Longitudinal slope of 3%
- One foot of drop between weirs
- Weirs 33 feet apart
- Low-flow notch sized for the minimum fish passage flow of 30 cfs
- Weirs arched upstream to increase stability and direct flow to center of channel
- Weirs sloped at 3% towards center of channel
- Most upstream weir is flat and one foot above the dam foundation

# Initial Design



# Initial Material Sizing

- Calculated the size of the weir boulders, engineered streambed material (ESM), and bankline rock mix for 30 cfs, 200 cfs, and 15,000 cfs using equations in the DFG Manual
- Results:
  - Boulders 3 to 4 foot diameter
  - Bankline Rock Mix – Particle sizes ranged from 1.3 feet down to silt
  - ESM – Particle sizes ranged from 1 foot down to silt

# Flood Control Guidelines

- We designed the initial roughened channel to meet the Central Valley Flood Protection Board's guideline of a 0.1-foot maximum water surface rise for the 100-year event due to the project
- However, San Joaquin County , who were initially fine with the project as a pilot project, later stated that they wanted a maximum water surface rise of no more than 0.0 feet due to the project

So...


The design had to change and the project became a rock ramp roughened channel

# Rock Ramp


- Took the previous design and filled in the pools to lower the hydraulic roughness during high flow events
- Left the boulder weirs from the initial design as grade control
- Kept the bankline rock and ESM mixes the same

**Rock ramp roughened channel design with a central low-flow channel**

**Added individual boulders both inside and outside of the low-flow channel to increase flow complexity and provide resting areas**




**Plan View**




**Profile View**

**Project footprint roughly 250 feet by 130 feet**




**Profile Detail**

- WEIR PLACEMENT NOTES:**
1. OVEREXCAVATE TRENCH ALONG ENTIRE LENGTH OF WEIR
  2. PLACE ENGINEERED STREAMBED MATERIAL (ESM) AS ROCK WEIR BEDDING
  3. PLACE WEIR BOULDERS ON ESM BEDDING
  4. BACKFILL ALL VOIDS BETWEEN BOULDERS WITH ESM
  5. WASH ESM WITH WATER AND TAMP TO FILL VOIDS BETWEEN WEIR BOULDERS AND WITHIN ESM
  6. PLACE ESM TO FINISHED GRADE
  7. WASH ESM WITH WATER TO FILL VOIDS WITHIN ESM AND ENSURE ABOVE GRADE FLOW, MINIMIZING FLOW THROUGH THE ESM
  7. PLACE HAND-SELECTED 10" TO 12" BOULDERS WHERE REQUIRED TO FILL GAPS BETWEEN BOULDERS.



**Boulder Weir Section**



**Roughened Channel Section**

- PLACEMENT NOTES:**
1. MIX ESM ON SITE TO ENSURE THE INDICATED MATERIAL GRADATION IN THE ESM TABLE.
  2. PLACE ESM IN 8" MAX LIFTS, TAMING TO COMPACT EACH LIFT.
  3. WASH EACH LIFT WITH WATER TO ENSURE THAT ALL AIR VOIDS ARE FILLED, AND THE ESM IS NOT ALLOW SUBSURFACE WATER TO FLOW THROUGH VOIDS.
  4. IF WATER FLOWS THROUGH VOIDS, PLACE ADDITIONAL FINE-GRAINED MATERIAL ABOVE THE LIFT AND WASH WITH WATER. CONTINUE THIS PROCESS UNTIL THE ESM DOES NOT DRY WATER TO FLOW BELOW ITS SURFACE.
  5. UPPER 15" OF ESM MUST BE ROUNDED RIVER-RUN MATERIAL THROUGHOUT LIMIT OF WORK.
  6. THE UPPER 35" OF ESM WITHIN 10 FEET DOWNSTREAM OF EACH WEIR MUST BE ROUNDED RIVER-RUN MATERIAL.
  7. THE LOWER PORTIONS OF ESM NOT MENTIONED ABOVE MAY BE ANGULAR ROCK MEETING THE GRADATION IN THE ESM MATERIAL TABLE.

FINISHED GRADE ELEVATION CONSTRUCTION TOLERANCES	
BANKLINE ROCK MATERIAL	-0.5' TO +0.5'
ENGINEERED STREAMBED MATERIAL	-0.25' TO +0.25'
TOP OF WEIR CREST BOULDERS	0.0' TO +0.5'

ENGINEERED STREAMBED MATERIAL	
1 PART	10" TO 12" BOULDERS
2 PARTS	5" TO 10" COBBLES
8 PARTS	3.5" TO 5" COBBLES
8 PARTS	0.3" TO 2.5" GRAVEL
3 PARTS	0.06"-0.3" FINE GRAVEL
2 PARTS	< 0.06" FINES

BANK	
5 PARTS	10" TO 12" BOULDERS
5 PARTS	5" TO 10" COBBLES
7 PARTS	3.5" TO 5" COBBLES
2 PARTS	0.3"-2.5" GRAVEL
2 PARTS	0.06"-0.3" FINE GRAVEL
1 PART	FINES

NOTE: MIX MATERIAL ON SITE.

**NOTES:**

1. LOCAL SURFACE IRREGULARITIES OF THE ABOVE MATERIALS MUST FALL WITHIN THE ABOVE TOLERANCES.
2. THE MEAN DIFFERENCE BETWEEN AS-BUILT AND DESIGN ELEVATIONS OF ANY 5 POINTS TAKEN 20' MINIMUM BETWEEN POINTS ALONG THE FINISHED GRADE OF THE UPSTREAM-MOST WEIR (STA. 8+47.73) MUST HAVE A MAXIMUM VALUE OF 0.10'.

# Presentation Outline

- Colleagues, Partners, and Roles
- Background
- Fish Passage Issues at Budiselich
- Design
- **Construction**
- Monitoring

# Groundbreaking - September 6, 2011



**September 8, 2011 Pre-Construction**



**Construction Began on  
September 12**

**Materials being stockpiled**

**Water pumping  
and conveyance**


**Cardinal Ave**

**Google Earth – September 15**



**September 16, 2011**

**Excavation of native material  
down to subgrade elevation**



**September 16, 2011**


**Excavation of native material  
down to subgrade elevation**



September 16, 2011



Some of the Engineered  
Streambed Material  
Components



September 20, 2011



**Mixing the Engineered  
Streambed Material**

September 20, 2011



**The Mixed Engineered  
Streambed Material**

**September 16, 2011**



**Weir Boulders**

September 20, 2011



Trench for the 1<sup>st</sup> Weir

September 20, 2011



Bank key for the 1<sup>st</sup> weir

September 22, 2011

Keyed into the bank

The 1<sup>st</sup> weir



September 23, 2011

The finished  
1st weir

The partial 2nd weir





FPIP also provided  
construction  
staking and  
elevation surveys



September 23, 2011

# Overview of Construction



**Boulder Weirs**


**Jetting ESM into  
boulder voids**

September 26, 2011



**Washing of Engineered  
Streambed Material to fill voids**

September 26, 2011



**Individual Boulders**

**Finished Grade of Engineered  
Streambed Material**

**September 27, 2011**

**The downstream end of the roughened channel showing the last weir and the bankline rock**





3

2


1

**Overview of project and alignment of weirs**

**October 3, 2011**

**October 12, 2011**

**After construction looking downstream**



**Low-flow Channel**

**Weir 1**

**October 12, 2011**

**After construction looking upstream**




# Project Cost

- USFWS = ~ \$155,000
- SEWD = ~ \$155,000
- DWR FPIP = ~ \$150,000
- DFG = \$39,000
  
- TOTAL = ~ \$500,000

# Presentation Outline

- Colleagues, Partners, and Roles
- Background
- Fish Passage Issues at Budiselich
- Design
- Construction
- **Monitoring**

## 2011 Pulse Flow Releases to Benefit Fish



**October 18, 2011 – 36 cfs**



**October 18, 2011 – 36 cfs**




**October 18, 2011 – 36 cfs**



**Individual boulders in low-flow channel create flow complexity**

Station (ft)	Depth (ft)	Velocity (ft/s)	Notes
	<b>1.15</b>	<b>0.83</b>	<b>dam foundation</b>
0	0.9	3.06	weir 1
6	1.3	5.33	downstream of weir 1
17	1.4	6.12	at constricting boulders
<b>33</b>	<b>0.9</b>	<b>7.70</b>	<b>at weir 2</b>
33	0.8	3.36	2' from left edge
49	1.3	3.84	at constricting boulders
65	1.1	5.37	at weir 3
87	1.5	6.54	at boulder between weirs 3 and 4
98	1.0	5.68	at weir 4
121	1.0	5.14	between weirs 4 and 5
135	1.0	5.02	at weir 5
155	2.6	0.58	in backwater area



**36 cfs flow monitoring**

November 2, 2011 – 150 cfs



**November 2, 2011 – 150 cfs**



**November 2, 2011 – 150 cfs**



Station (ft)	Depth (ft)	Velocity (ft/s)	Notes
0	1.6	2.3	Dam foundation
5	1.0	4.6	at weir 1 (fish observed passing)
10	1.3	4.8	5' downstream of weir 1
20	1.2	5.0	at constricting boulders
38	1.6	6.0	at weir 2
50	2.4	4.8	3' upstream of boulders between weirs 2 and 3
53	2.1	7.4	at boulders between weirs 2 and 3
66	2.1	6.3	6' upstream of weir 3
72	2.1	6.1	at weir 3
87	2.9	3.3	midway between weirs 3 and 4

# 150 cfs flow monitoring




**We did see a fish pass at this location**

**November 2, 2011 –  
Approximately 150 cfs**

**Resting areas behind boulders**



**November 2, 2011 – 150 cfs**



**Depths outside of the low-flow channel were 7 – 9”  
and velocities ranged from 1.5 – 4.2 fps**

**November 3, 2011 - 300 cfs**



**November 3, 2011 - 300 cfs**



**Shows the resting areas behind the boulders**

**October 18, 2011 – 36 cfs**

**Next 3 slides show the  
same camera angle at 3  
different flows**



**November 2, 2011 – 150 cfs**




**November 3, 2011 - 300 cfs**



**November 15, 2011**

**After initial pulse flow**

- **no major changes outside low-flow channel**
- **movement of material in low-flow channel**



**November 15, 2011**



**November 15, 2011**



**February 7, 2012**



**Transported ESM in lower low-flow channel, generally 4 - 5" and lower in size**

**February 7, 2012**

**Upper end of low-flow channel much coarser  
and boulders have been scoured**

# Why did this material move?

- During design
  - our initial ESM calculations gave 9" as the largest particle size
  - we sized up to 12" since we used rounded material
  - shear stress calculations gave 6" as the largest particle that should move in the low-flow channel (we did account for an instantaneous maximums and a factor of safety) – Fischenich 2001
  - we thought that the larger material would help to hold the smaller material in place
- However,
  - while we expected some movement of ESM, the magnitude was greater than we anticipated
  - we believe that the individual boulders produced flow patterns that created significant scour areas
  - local residents created small dams to poach fish which caused localized increases in channel slope and subsequent scour

February 7, 2012



# Fish Passage Conclusions

- Although no studies were completed to assess the passage efficiency of the project,
- the measured depths and velocities are well within the range of salmonid swimming abilities, and
- there are resting areas so fish do not have to pass the whole project at once
- In addition, it was estimated that over 400 fall-run Chinook passed upstream of the project
- Therefore, we believe that we met the fish passage goal of the project

# Lessons Learned


- Look for ways to reduce the project footprint to reduce project costs and environmental impacts
- Rock Ramp Low-flow Channel
  - In adding flow complexity, smaller material can move if significant amounts of larger material are not present
  - Need to coarsen the low-flow channel by increasing the percentage of larger material
  - Need to increase size of individual boulders in the low-flow channel
  - Perhaps make the low-flow channel a step-pool design



**We are currently in design on two other projects in the system**

**Central California Traction  
Railroad Crossing**

# Caprini Low-water Crossing



# Thank you



<http://www.water.ca.gov/fishpassage>