2010 Urban Water Management Plan

Final

Prepared for:

Castaic Lake Water Agency (CLWA)
CLWA Santa Clarita Water Division
Newhall County Water District
Valencia Water Company
(Los Angeles County Waterworks District No. 36/Cooperating Agency)

Prepared by:
Kennedy/Jenks Consultants
Nancy Clemm , P.E.
Luhdorff & Scalmanini Consulting Engineers
Stacy Miller Public Affairs

June 2011

model studies of SWP operations. In general, DWR model studies show the anticipated amount of SWP supply that would be available for a given SWP water demand, given an assumed set of physical facilities and operating constraints, based on 82 years of historic hydrology. The results are interpreted as the capability of the SWP to meet the assumed SWP demand, over a range of hydrologic conditions, for that assumed set of physical facilities and operating constraints.

DWR's 2009 update of the *Reliability Report* presents the results of model studies for years 2009 and 2029. In these model studies, DWR assumed existing SWP facilities and operating constraints for both the 2009 and 2029 studies. The primary differences between the two studies are an increase in projected SWP contractor demands, an increase in projected upstream demands (which affects SWP supplies by reducing the amount of inflows available for the SWP), and the inclusion in the 2029 study of potential impacts on historic hydrology of the effects of climate change and accompanying sea level rise. In the report, DWR presents the SWP delivery capability resulting from these studies as a percent of maximum contractor Table A Amounts. To estimate supply capability in intermediate years between 2009 and 2029, DWR interpolates between the results of those studies.

6.3 Normal, Single-Dry, and Multiple-Dry Year Planning

The water suppliers have various water supplies available to meet demands during normal, single-dry, and multiple-dry years. The following sections elaborate on the different supplies available to the water suppliers including groundwater, recycled water and imported supplies.

6.3.1 Groundwater

In accordance with the groundwater operating plan for the basin, groundwater supplies for all uses from the Alluvial Aquifer are planned to be in the range 30,000 to 40,000 AFY in average years and 30,000 to 35,000 AFY in dry years; supplies from the Saugus Formation are projected to be 7,500 to 15,000 AFY in average years and 15,000 to 35,000 AFY in dry years. The updated Basin Yield analysis (LSCE and GSI, 2009) concluded pumping in those ranges to be sustainable. While there is sufficient Alluvial pumping capacity to achieve the Alluvial groundwater supply (Table 3-8), it is planned that VWC will develop some future capacity as it constructs municipal supply wells to replace existing agricultural wells when planned development converts existing agricultural land use to municipal land use. Existing Saugus pumping capacity is sufficient to achieve about 27,000 AFY (Table 3-9), or about 77 percent of the upper end of the Saugus operating plan. Hence, it is planned that restored capacity (VWC Well 201) and future Saugus pumping capacity (new wells) will be added to achieve the full range of the Saugus operating plan.

The existing and planned groundwater supplies used in this Plan are generally the pumping rates, within the operating plan ranges, that were analyzed in the Basin Yield update. As such, they tend toward the upper ends of the respective ranges except for normal year Saugus pumping, which is closer to mid-range of the Saugus operating plan. For the multiple-dry year period, it was assumed that pumping from the Saugus Formation would be governed by the groundwater operating plan summarized in Table 3-5, with average pumping over the 4-year dry period of about 21,500 AFY. Total projected Alluvial and Saugus pumping, including pumping by the purveyors and by agricultural and other users, is shown by year type in Tables 3-7 to