


- 1 CHAF GUARD
- 2 GUY WIRE. REMOVE ONCE TREE HAS DEVELOPED ADEQUATE ROOTS FOR SUPPORT
- 3 GUYING STAKE. REMOVE WITH GUY WIRE
- 4 TOP OF ROOTBALL SHALL BE SET 1"-2" ABOVE FINISH GRADE
- 5 4" HIGH WATER BASIN. ROLL FLUSH WITH SURROUNDING GRADE ONCE PLANT IS ESTABLISHED
- 6 FINISH GRADE
- 7 MULCH. SEE PLANTING SPECIFICATIONS. MULCH SHALL BE KEPT 4" AWAY FROM BASE OF TREE
- 8 BACKFILL MIX PER SOIL TEST
- 9 MYCORRHIZAL PACKETS: SEE PLANTING SPECIFICATIONS
- 10 PLACE ROOTBALL ON NATIVE SUBGRADE
- 11 FILTER FABRIC

TREE PLANTING 1
NTS



CH2MHILL
U.S. ARMY ENGINEER DISTRICT
LOS ANGELES
CORPS OF ENGINEERS
DESIGNED BY: C SLATER
DRAWN BY: A GORDEN
CHECKED BY: FECHAL
SUBMITTED BY: ART JUNG, P.E.
CHEF, DESIGN BRANCH
L.A. DISTRICT FILE NO. XXX-XXXX
SPEC. NO. : NOT APPLICABLE
CADD FILE NAME: PDF1501d.dgn

EASTERN MUNICIPAL WATER DISTRICT
PERRIS II DESALINATION FACILITY
PERRIS, CALIFORNIA
**TYPICAL PLANTING
DETAILS**

SYMBOL	DESCRIPTIONS	DATE	APPROVAL