



1. TOP OF PLATFORM SHALL HAVE A MINIMUM OF 6" STICK-UP ABOVE FILL DURING PLACEMENT AND 1' AFTER PRELOAD IS COMPLETE.
2. 4" PVC PIPE AND CAP TO BE INSTALLED AFTER FINAL FILL ELEVATION HAS BEEN ACHIEVED.

## TYPICAL SETTLEMENT PLATFORM

NTS

3163-107