

Multi-Level Monitoring Well Quote for Castaic Lake Water Agency

BID SCHEDULE OF ITEMS AND PRICES

Item	Description	Estimated Quantity	Unit	Unit Price	Total Amount
1	Mobilization and demobilization, including fencing **Including hauling fluids and cuttings	1	lump sum	\$ <u>93,000.</u>	\$ <u>93,000.00</u>
2	(Contractor's option) Conductor casing installation	50	linear foot	\$ <u>412.</u>	\$ <u>20,600.00</u>
3	Drill 14-inch borehole	1200	linear foot	\$ <u>83.</u>	\$ <u>99,600.00</u>
4	Geophysical survey (spontaneous potential, single-point, 16-inch normal, 64-inch normal, guard, gamma ray, and caliper)	1	lump sum	\$ <u>8,200.</u>	\$ <u>8,200.00</u>
5	Furnish and install 3-inch, Sch. 80 PVC casing	2750	linear foot	\$ <u>18.</u>	\$ <u>49,500.00</u>
6	Furnish and install sand filter pack	200	linear foot	\$ <u>42.</u>	\$ <u>8,400.00</u>
7	Furnish and install grout seal	1000	linear foot	\$ <u>43.</u>	\$ <u>43,000.00</u>
8	Mechanical and pump development (swab, bail, airlift)	40	hour	\$ <u>425.</u>	\$ <u>17,000.00</u>
				Grand Total	\$339,300.00

Submitted by: Thomas Nanchy-Account Manager

Signature and Title



Layne Christensen Company

Company

1717 West Park Avenue Redlands California 92337

Address

510011

California C57 License No.

(909) 390-2833

Telephone Number

7-3-12

Date