

## Attachment 8. Quality Assurance

---

This Quality Assurance, Attachment 8, presents functions, procedures, and specific quality assurance (QA) and quality control (QC) activities that will be used for each task of this proposed project. Attachment 8 provides procedures for planning, implementation, and assessment in the collection of information and production of project deliverables to ensure data and deliverables are useful for the purposes for which they are intended. The procedures described herein are designed to ensure that precise, accurate, representative, comparable, and complete data are collected throughout the data collection program and so that project deliverables (reports, groundwater models, etc..) receive the appropriate review by qualified individuals.

### Personal Qualifications

The key personnel roles and qualifications for the team that will carry out this project are:

- **Project Manager** – The Project Manager (PM) is responsible for overall project planning and execution including: establishing project objectives, scope, budget, schedule, preparing final submittals, and coordinating with the team. The PM will have managed similar project prior to this assignment and will be responsible for the implementation of quality procedures and will, as necessary, perform audits, surveillance, and document reviews. The PM will initiate corrective actions, and be responsible to review laboratory data. The Project Manager has the authority to stop work if quality procedures are not followed.
  - **Project California Certified Hydrogeologist (CHG)** – groundwater activities, data collection and reporting will be conducted under the supervision of a CHG. The project CHG will have over 10 years of professional experience and will oversee work plan development, data collection, well drilling and installation activities, groundwater sampling and analysis, data review and reporting.
  - **California Project Engineer (PE)** – Engineering activities will be conducted under the direction of a California professional civil engineer. The California PE will have over 10 years of professional experience and will oversee production of design documents and calculations and will sign and stamp engineering drawings and engineering reports.
  - **Field Staff** – Field personnel that participate in field work and sampling will have reviewed the site-specific plans and will be trained prior to the first sampling event in sample collection procedures (including QA/QC, grab sampling techniques, completing laboratory chain-of-custody forms, and the proper handling of samples), and field analysis (including instrument calibration, data recording procedures, and interpretation of collected data).
-

## **Procedural Assurances**

All project documents and deliverables will be produced in accordance with an efficient process that includes: assigning a lead author responsible for deliverable content and meeting schedule, producing draft and final versions of each deliverable, technical review of draft versions by the appropriate technical lead, and conducting final work product review by the project manager.

- Reports and Documents: each document will be signed by the appropriate technical leader: engineering documents will be signed by the responsible PE, groundwater documents will be signed by the responsible CHG. .
- Calculations: calculations that are made as part of this investigation will be reviewed by the appropriate technical leader. For example, groundwater gradients and contours will be reviewed and approved by the project CHG. Engineering calculations will be reviewed by the PE.
- Field Records: all field records, including: field data sheets documenting results of field tests and QC samples; field forms documenting equipment maintenance and calibration; and, sample collection and handling documentation (copies of chain-of-custody forms, shipping receipts, etc.) will be reviewed by the senior technical lead and archived in project files.

## **Health and Safety**

To protect workers during the project, a site-specific Field work Safety Plan (FWSP) will be prepared. The FWSP will describe the safe use of equipment, evaluation of hazards, safe site investigation procedures, personal protective equipment, emergency procedures, and training required to conduct the project work activities.

Activities conducted at the Site will be in compliance with applicable Occupational Safety and Health Administration (OSHA) regulations, particularly those in Title 29 of the Code of Federal Regulations, Parts 1910 and 1926 (29 CFR 1910 and 29 CFR 1926), and other applicable federal, state, and local laws, regulations, and statutes. A copy of the FWSP will be kept on site during scheduled field activities

## **Standardized Methodologies**

Technical activities undertaken for this project will use standardized methodologies that accepted to meet or exceed industry standards. These methodologies include standard operating procedures (SOPs, ASTM methods, California state standards, and local standards and regulations.

- Utility clearance – all invasive subsurface activities for this project will include utility clearance to ensure drilling and excavation locations are safe. Utility location will include contacting Underground Service alert, and conducting boring clearance and utility locations surveys on the site prior to beginning work.
  - Well Drilling - Well Drilling will be conducted in accordance with ASTM D5783-95, a Standard Guide for Use of Direct Rotary Drilling with Water-based Drilling fluid
-

for Geoenvironmental Exploration and the Installation of subsurface water-quality monitoring devices.

- Well installation and development – Monitoring wells will be installed to comply with the California Water Well Standards as defined in Bulletin 74-81 and updated in Bulletin 74-90, and in accordance with Section 13801 of the California Water Code. Well installation will comply with local regulations for well construction. Well development will be conducted in accordance with ASTM Standard D5521 – Development of Groundwater Wells in Granular Aquifers. To ensure the well will perform for its intended use. Development will consist of a series of bailing, pumping, and surging to remove residual fine grained material and ensure proper filter pack. Upon completion of the installation, monitoring well descriptions will be filed with DWR/CASGM in accordance with DWR requirements.
- Soil classification/soil description – Soils encountered during sampling events and well drilling will be classified in accordance with the Unified Soil Classification System (ASTM D2487). USCS descriptions will be included on well and soil boring logs.
- Field data measurements (water level, pH, temperature, electrical conductivity, oxidation reduction potential, dissolved oxygen, and turbidity) - Field measurements will be collected using portable meters and/or field test kits that follow EPA-approved methods. Field instruments will be calibrated daily, and measurements taken using the procedures recommended by the manufacturer of the meter or test kit. Field instruments will be calibrated according to the schedule recommended by the manufacturer. Calibrations that are performed by personnel in the field may also be recorded on the field data sheets to indicate which samples were analyzed pre- and post-calibration for the specific sampling event. If calibration is not successful or other issues pertaining to calibration arise, the equipment manufacturer will be contacted to determine the appropriate corrective action; the problem and corrective action will be documented in the maintenance/calibration logbook. Results of field measurements will be recorded on field data sheets.
- Borehole geophysical logging – downhole logging by geophysical methods may be necessary to assess the stratigraphy, integrity of the borehole, or the diameter of the borehole prior to well installation. Planning for geophysical logging will be completed in accordance with ASTM D5753 to assess and select the appropriate method. Geophysical logging will be conducted in accordance to individual method requirements such as ASTM D6167 (Caliper log), ASTM D6274 (Gamma log), ASTM D6727 (Neutron logging).

### **Quality Requirements for Materials Selection**

Materials to be selected for this project will consist primarily of well construction materials. Prior to any well construction activity the field leader will conduct an inspection of materials and supplies to make sure they are appropriate for the task. Sampling materials inspections will include review of field test equipment condition; confirm calibration standards are

---

within date, inspect sample containers and preservatives for applicability to the desired methods. During well construction, the field staff will inspect and verify that materials to be used in well construction meet the requirements and specifications of the well design. Specific items that will be reviewed include cement and bentonite type and quantities, filter pack sand specifications and quantities, well casing material specifications and condition, well screen size and condition. Any material that does not meet design requirements will be rejected.

---