Multi-Level Monitoring Well Quote for Castaic Lake Water Agency

BID SCHEDULE OF ITEMS AND PRICES

Item	Description	Estimated Quantity	Unit	Unit Price	Total Amount
1	Mobilization and demobilization, including fencing **Including hauling fluids and cuttings	1	lump sum	$ 93,000.	$ 93,000.00
2	**(Contractor's option)** Conductor casing installation	50	linear foot	$ 412.	$ 20,600.00
3	Drill 14-inch borehole	1200	linear foot	$ 83.	$ 99,600.00
4	Geophysical survey (spontaneous potential, single-point, 16-inch normal, 64-inch normal, guard, gamma ray, and caliper)	1	lump sum	$ 8,200.	$ 8,200.00
5	Furnish and install 3-inch, Sch. 80 PVC casing	2750	linear foot	$ 18.	$ 49,500.00
6	Furnish and install sand filter pack	200	linear foot	$ 42.	$ 8,400.00
7	Furnish and install grout seal	1000	linear foot	$ 43.	$ 43,000.00
8	Mechanical and pump development (swab, bail, airlift)	40	hour	$ 425.	$ 17,000.00

Grand Total $339,300.00

Submitted by: Thomas Nanchy-Account Manager
Signature and Title

Layne Christensen Company
Company

1717 West Park Avenue Redlands California 92337
Address

510011
California C57 License No.

(909)390-2833
Telephone Number

7-3-12
Date