

#### 5 Attachment 5 - Work Plan

The following sections provide a detailed description of the Work Plan.

#### 5.1 Scope of Work

This project proposes to construct three stream gauging sites, install water level transducers at four existing well sites, install one weather station in the watershed tributary to the Los Banos Creek Detention Reservoir, and modify a website to accept and display real-time information from each of the sites mentioned above (see Exhibit 5.1). The project has been preliminary designed, however finalization of the design, environmental compliance, and permit acquisition have yet to be performed. Data regarding water quality, depth and flow rates will be collected on a regular basis after completion, to ensure all devices are working correctly. Quarterly reports will be prepared throughout the contract period, followed by the Final Report document the achievements of the project. The tasks and subtask necessary for successful implementation are described below.

#### 5.2 Tasks and Subtasks

In an effort to better understand the parameters of the program and the magnitude of its effectiveness, implementation of the various monitoring and recording devices are necessary. The tasks laid out below demonstrate the path necessary for successful project completion and grant administration should the project be funded.

#### 5.2.1 Task 1 - Design, Environmental and Permitting

#### 5.2.1.1 Subtask 1.1 - Design

Civil design is only required on the stream gauging sites. The other improvements will be the installation of "out-of-the-box" devices provided by manufacturers based on their parameters. Design of the stream gauges will require some topographic surveys. This topographic data will be used to model the stream at different flow rates, to ensure that improvements do not impact the creeks operational capacity. Designs will then be prepared to construction level detail, for CCID staff to construct the gauges. In the same trip to survey the channel, surveys will also be performed to identify the reference elevation at each of the monitoring wells, and collect the location and elevation of the weather station.

#### 5.2.1.2 Subtask 1.2 - Environmental Compliance

It is believed that the nature of the work is categorically exempt from CEQA requirements, and as appropriate, a Categorical Exemption (Class 6 'Information Collection – Section 15306 or Class 3 'Small New Facilities – Section 15303') for the work will be completed, adopted by the SJRECWA Board of Directors, and filed with the County. However, if it is determined that further environmental documentation is needed; the required CEQA documentation will be prepared by an appropriate environmental professional. Environmental issues regarding threatened and endangered species, potential mitigation measures, and other CEQA/NEPA requirements, for example cultural resources or air quality concerns, will be investigated. Provisions for fish and wildlife protection and discussion of environmental and ecological problems unique to this project will also be addressed. Once the improvements are selected, if appropriate an Initial Study for CEQA will be prepared to determine if an Environmental Impact Report or a Negative Declaration is the more appropriate CEQA document. This



will include an environmental assessment by a licensed wildlife biologist at each viable site and other technical studies as needed. Subsequent to the Initial Study, the appropriate environmental documents (EIR or Negative Declaration) may be recommended. If mitigation measures are identified as necessary, a Mitigation Monitoring and Reporting Plan will be completed. Additionally, the lead agency will complete the proper noticing requirements in accordance with CEQA Guidelines. SJRECWA's counsel will provide needed agreement documentation for right-of-way and entry permission for monitoring of wells.

#### 5.2.1.3 Subtask 1.3 - Permits

The stream gauges will be impacting a natural stream, but for the most part will be placed in existing disturbed areas at canal and/or road crossings. Typically, this will require that a Department of Fish and Game Section 1602 Streambed Alteration Agreement. The standard notification form (FG2023) will be filed with DFG for the Streambed Alteration Agreement.

#### 5.2.2 Task 2 - Construction and Implementation

Construction will be performed by CCID staff. CCID has a large crew that routinely performs construction throughout this District. This workforce increases when water is not being delivered, as ditchtenders transfer to maintenance and construction. In addition to construction crews, the District also has a SCADA technician capable of the installation of all the remote monitoring devices.

#### 5.2.2.1 Subtask 2.1 - Construct Stream Gauges

Three locations have been identified as ideal locations for stream gauging, where Los Banos Creek crosses the follow facilities:

- 1. Delta Mendota Canal
- 2. CCID's Outside Canal
- 3. CCID's Main Canal



#### 5.2.2.1.1 LBC at the Delta Mendota Canal

The first site will be located at the intersection of the Delta Mendota Canal (DMC) and the Los Banos Creek. Currently at this site exists 6 corrugated metal pipe arch culverts, roughly 6' tall by 10' wide (see plan, Exhibit 5.2). At this site it is proposed that a Sontek IQ-Plus (or equivalent) be installed in each of the culverts (see product literature, Exhibit 5.3). This will allow for flow measurement without having to disturb the existing channel or structure. The Sontek IQ-Plus uses acoustic Doppler flow measurement technology. These meters will be installed per the manufacturer recommendation. All of the flow meters will deliver their information to a solar powered Nexsens – iSIC Web Enabled Data logger (see product literature, Exhibit 5.4) in a cabinet located at the top of the channel bank adjacent to the culverts. This data will be transmitted back to the server and website via cellular communications. A staff gauge will be placed upstream for visual verification of flow rate.

Minimum construction will be required for this option. The first step will be locating and installing the mounting brackets for the flow meters. Next, conduits and pull boxes will be placed as necessary for the wiring to be routed the data logger adjacent to the culverts.




Figure 1. Site Photo of LBC Culverts near DMC

#### 5.2.2.1.2 LBC at the CCID Outside Canal

The second site will be located at the intersection of Los Banos Creek with the CCID Outside Canal. A concrete lined control section will be constructed between existing concrete abutments at the site (see plan, **Exhibit 5.5**). This control section will be rectangular in shape, roughly 10-feet wide and 100-feet long. A weir plate will be installed on the upstream end of the concrete lined section, stretching the width of the section. This will act as a flow measurement device. Real time data will be collected by using a level transducer located in a stilling well upstream of the weir plate. The depth measured by the transducer will be relayed to the website via a solar powered YSI – EcoNet Web Enabled Data logger (see product literature, **Exhibit 5.7** and **Exhibit 5.8**), and will then be translated into a flow rate, based on a head-discharge relationship.



Construction will begin with clearing and grubbing of all vegetative material within the limits of work. The ground will then be graded and compacted to a minimum of 90% relative compaction. Next, formwork and rebar will be constructed, and then the concrete will be poured into the forms and consolidated into place with by screeding. An 18" diameter stilling well will be installed adjacent to the creek, with a 4" diameter pipe connecting the stilling well to the channel. Finally the electronics (transducer and data logger package) will be installed to manufacturer recommendation, and integrated into the system.



Figure 2. Site Photo of LBC Crossing of CCID Outside Canal

#### 5.2.2.1.3 LBC at the CCID Main Canal

The third site will be located at the intersection of Los Banos Creek with the CCID Main Canal. A trapezoidal concrete lined control section will be constructed upstream of an existing bridge at the site (see plan, Exhibit 5.6). This control section will be trapezoidal in shape, matching the existing channel width of about 40 feet and 10-feet long. A weir plate will be installed on the upstream end of the concrete lined section, stretching the width of the section. Vertical sidewall plates will be added to create a contracted rectangular weir to eliminate the effects of the trapezoidal shape and its inherent change in weir length with changes in depth. This weir will act as a flow measurement device. Real time data will be collected by using a level transducer located in a stilling well upstream of the weir plate. The depth measured by the transducer will be relayed to the website via a solar powered YSI – EcoNet Web Enabled Data logger (see product literature, Exhibit 5.7 and Exhibit 5.8), and will then be translated into a flow rate, based on a head-discharge relationship.

Construction will begin with clearing and grubbing of all vegetative material within the limits of work. The ground will then be graded and compacted to a minimum of 90% relative compaction. Next, formwork and rebar will be constructed, and then the concrete will be poured into the forms and consolidated into place with by screeding. An 18" diameter stilling well will be installed adjacent to the creek, with a 4" diameter pipe connecting the stilling well to the channel. Finally the electronics



(transducer and data logger package) will be installed to manufacturer recommendation, and integrated into the system.



Figure 3. Site Photo of LBC Crossing of CCID Main Canal

#### 5.2.2.2 Subtask 2.2 - Install Monitoring Well Water Level Sensors

Transducers will be placed in 4 wells located in adjacent properties along the Los Banos Creek (site indicated by red circles on Exhibit 5.1). The complete setup will use a YSI – EcoNet Web Enabled Data loggers, with a YSI – 600LS Level Sonde water level transducers (see product literature, Exhibit 5.7 and Exhibit 5.8). The Level Sonde determines the depth of the water over the transducer, this is then relayed to the EcoNet which translates to a depth-to-water measurement, which will be transferred to the website via a cellular network. The installation instructions will be followed as provided by the manufacturer. YSI instructs the end-user to install the battery, connect the field cable, and lower to the appropriate depth. The EcoNet will be pole mounted near the well. CCID is aware of and will follow the electrical codes that are required for this type of installation.

#### 5.2.2.3 Subtask 2.3 - Install Weather Station

In the watershed tributary to Los Banos Creek Detention Reservoir, a weather station will be installed for improved data to allow for improved reservoir operations. It is desired to install a Nexsens WS-100 total weather station (see product literature, **Exhibit 5.9**). This is equipped with a Vaisala WXT520 Multi-Parameter Weather sensor. This sensor is capable of measuring 6 different weather parameters: humidity, rainfall, temperature, barometric pressure, wind speed, and wind direction. Additionally, this weather station includes a data logger, cellular modem, and solar panel. The station will be in a representative area, free from turbulence caused by nearby objects, such as trees and buildings. At a minimum, on open area based on 150-meter radius from the weather station will be created. Since the device is battery powered, electrical service will not be required to be brought to the site.



#### 5.2.2.4 Subtask 2.4 - Website Modification

Grassland Water District's website has room to accept and display the 8 proposed real-time data monitoring sites. This website is maintained in-house by Grassland Water District. A link will be created on the home page labeled "LBCDR Real Time Monitoring". When directed to its page, a short description of the project will be provided along with a map displaying icons of the remote monitoring sites and their status (green- working, or red- not working). Each icon will be a link to each individual monitoring site's page that will display the real-time data. These links will not be password protect so that anyone interested in the operations has access to the information. Each of the SJRECWA Member agencies will also host links to this site.

#### 5.2.3 Task 3 - Data Analysis and Reporting

#### 5.2.3.1 Subtask 3.1 - Perform Field Data Collection

• Water Quality - Constituents of concern in the area are TDS, Nitrate, Arsenic, and Chromium VI. Each monitoring well site within network will be sampled and analytically tested for these constituents before and after a flow event through the creek (assumed quarterly). One blank sample and one duplicate sample will also be collected for quality control. Wells will be properly bailed to obtain representative water from the formation. Protocols exercised by the analytical laboratory will be followed as well (see sampling protocols, Exhibit 8.1). Water levels will also be recorded when water quality samples are retrieved. All sampling will be conducted by appropriate professionals, with appropriate preservatives, under proper chain of custody procedures, and transported to the lab within the proper holding times. The results will be summarized and reviewed by a water quality specialist. The results will also be compared to other water quality test results in the area, state drinking water standards, and recommended values for irrigated agriculture.

#### Monitoring Site Accuracy Verification –

It is proposed that the remote monitoring sites be evaluated on the schedule below. This schedule is subject to change depending on how sites perform.

- Well Sites on a monthly basis the depth to water in wells will be measured using a sounder. This measurement will be compared to the same reference point of the realtime data monitoring device, to ensure the devices are reporting reasonable values.
- Stream Gauges On a bi-weekly basis during stream flow events, a current meter will be used to compare flow rates obtained by the real-time monitoring devices. Where a rated section is used, the constants of the equation may need to be adjusted.
- Weather Station Site visits with a thermometer on a bi-weekly basis will be done to confirm the accuracy of the weather station. In addition, while not completely representative, internet sources will be consulted which can be effective in identify problems when large difference exist.

#### 5.2.3.2 Subtask 3.2 - Quarterly Report

The Authority will submit required quarterly progress reports to DWR. These reports will discuss progress to date, data developed, information gained, costs incurred, and problems encountered. Each



report will be prepared in accordance with the required DWR format. Progress reports will also be provided to the Authority's Board of Directors.

#### 5.2.3.3 Subtask 3.3 - Final Reports

The Final report will include pertinent data, criteria, maps, narratives, alternatives, recommendations, and conclusions identified in this work plan. The report will also include an Executive Summary, a comparison between the planned schedule in the Agreement, actual timeline of completed tasks, and an explanation of differences, and discussion of major problems encountered and how they were resolved. This report will also include data collected pursuant to this grant, including the following:

- Location and description of sites included in monitoring network
- Summary of stakeholder participation in this project
- Screen shots of website
- Water level information
- Water quality test results
- Hydraulic and hydrologic information

A draft report will be submitted to DWR for review. The agency review period is anticipated to be up to three months. The Draft Report will also be available in the SJRECWA office for review by the public. SJRECWA will submit copies of the Final Report to DWR in the quantities requested. The final report will address comments from DWR on the draft report. The Final Report will also be available in the SJRECWA office for public review.

#### 5.3 Site Access

SJRECWA recognizes that acquiring access to property in a timely manner is critical to a timely completion of the project. The applicant will initiate obtaining permission for access to property early in the project stages, utilizing a Right-of-Entry form (see **Exhibit 5.10**). Time for obtaining property access is included as Subtask 1.3 in the project work plan, and allotted in the schedule.

#### 5.4 Performance of the Project

Project monitoring will be performed through the following:

- 1. Updates on the project status at monthly Authority Board meetings
- 2. Updates on the project status at annual grower's meetings
- 3. Quarterly progress reports submitted to DWR
- 4. Meetings with other water agencies to discuss project impacts to third-parties
- 5. Submitting groundwater level and quality data to DWR and USBR
- 6. The Draft Project Report will be available in the Authority office for public review and comments

These monitoring efforts will provide opportunities for the public, Authority staff, neighboring agencies, and DWR to comment on the project. Involvement of these parties will ensure that the work is proceeding in the appropriate direction and ultimately provides a product that is needed and understood.



Lastly, the QA/QC measures outlined in **Attachment 8**: Quality Assurance will also help to ensure that the project is properly monitored and reviewed.


#### 5.5 Information Dissemination


The goals of information dissemination for the Project include the following:


- 1. Educate public on the technical aspects of the project;
- 2. Educate public on available options for groundwater management;
- 3. Update public on progress;
- 4. Gauge public support; and
- 5. Collect and discuss comments and suggestions.

Information dissemination will be accomplished through the following methods, which the Authority already performs, and therefore will not add any extra burden:

- 1. Monthly public board meetings.
- 2. Updates about the proposed project will be published in the Authority quarterly newsletter over the life of the project.
- 3. Presentation and discussion of the project at the Annual Grower's Meeting.
- 4. Meetings with other agencies such as the San Luis Delta Mendota Water Authority.
- 5. The Draft Project Report will be available in the District office for the public to review.







# SonTek-IQ\*\*

Volume • Flow • Level • Velocity



- Flow/volume in 8cm (3 in) of water
- 5-beam pulsed Doppler design
- Modbus/SDI-12/RS232 ready
- Installs with limited or no earthworks
- Data you can make decisions on









Easy Set-up and Installation!

sontek.com



## TM SonTek-IC

Developed with assistance from the Cooperative State Research, Education, and Extension Service of the U.S. Department of Agriculture\*, the IO starts with a custom flow algorithm derived from


hundreds of field measurements. The four velocity beams profile water velocity both vertically and horizontally ensuring complete coverage of the velocity field. The built-in pressure sensor and vertical acoustic beam work in tandem to measure the water level. Simply input the channel geometry using the intuitive IQ software and you are outputting flow data in minutes.

Easy Installation: User friendly mounting brackets allow for the IQ to be installed by simply inserting two bolts 12.7 cm (5 in) apart along the centerline of the channel. The orientation of the slots on the mounting plate to allow users to orient the instrument in the direction of flow. Ultra-low power consumption allows for smaller solar panels and batteries – making monitoring less conspicuous.



Simple Integration: Stand alone monitoring? Use a Datalogger? How about an RTU? The SonTek-IQ supports communications via RS232, SDI-12 and Modbus. Simply connect your IQ and program your datalogger and you are ready to collect data - no clumsy converters - makes integrating the SonTek-IQ fast and simple. The SonTek Flow Display, with options for 4-20

mA outputs, integrates to everyday workflow, simply connect to the Tek-IQ and read flow read data in the field without connecting to Stop.



Example screenshot of the IQ SmartPage

- Self contained all-in-one design
- Proprietary flow algorithms for small irrigation canals
- Uses SonTek's exclusive SmartPulseHD adaptive sampling
- Self-calibrating water level using vertical beam and pressure
- Standard package includes, IQ Software, easy mounting hardware, cable, adaptor and power supply



SonTek/YSI 9940 Summers Ridge Road San Diego, CA 92121, USA Tel: +1 (858) 546-8327 Fax: +1 (858) 546-8150 Email: inquiry@sontek.com

#### SPECIFICATIONS

#### SonTek-IQ

Velocity Measurement

- -Sampling Range<sup>1</sup>
- -Number of Cells
- -Velocity Range
- -Resolution

#### Water Level

- -Vertical Beam Range
- -Pressure Sensor Range
- -Pressure Sensor Accuracy
- -Water Level Accuracy

#### Power

- -Input
- -Consumption<sup>2</sup>

- -Acoustic Frequency
- -(2) Along Axis Beams
- -(2) Skew Beams<sup>3</sup>

#### Communications

#### Data Storage<sup>4</sup>

Operating/Storage Temperature

Temperature Sensor

Tilt Sensor

0.08 - 1.5 m (0.3 - 5 ft)

1 (dynamic integrated cell)

±5 m/s (16 ft/s)

0.0001 m/s (0.0003 ft/s)

±1% of measured velocity, ±0.5 cm/s (0.2 in)

0.05 - 1.5 m (0.2 - 5 ft)

10 m (33 ft)

0.1% of full scale

0.1% of measured depth or ±0.003 m whichever is greater (0.01 ft)

#### 7-15 VDC

0.5 - 1.0 W (0.02 when idle)

#### 3.0 MHz

25° off vertical axis, along axis of channel

60° off vertical and 60° off center axis of channel

RS232, SDI-12, Modbus

4 GB (approximately 1 year)

-5 to 60° C (23 - 140° F)

#### Velocity Measurement

- -Sampling Range<sup>1</sup>
- -Number of Cells
- -Cell Size

Vertical Beam Range

Advanced Data Reprocessing

Increased Number of Data Fields

0.08 - 5.0 m (0.3 - 16 ft)

Up to 100


2 cm - 10 cm (0.8 - 4 in)

0.05 - 5.0 m (0.2 - 16 ft)

1 Reference from the bottom of the instrument, actual performance depends on environmental conditions 2 Depends on sample duration and sample interval, a typical deployment an sample duration of 2 minutes with a 15 minute sample interval consumes approximately 0.1 W on average.

3 Depending on site conditions, the skew beams allow for horizontal velocity profiling 3 times the measured depth. 4 Exact duration of data storage depends on instrument deployment; time estimate presented here is based on a





SonTek/YSI, founded in 1992 and advancing environmental science in over 100 countries, manufactures affordable, reliable acoustic Doppler instruments for water velocity measurement in oceans, rivers, lakes, harbors, estuaries, and laboratories. SonTek, and SonTek-IQ are trademarks of YSI Inc., Yellow Springs, OH, USA. The SonTek-IQ is made in the USA. Specifications are subject to change without notice. This material is based upon work supported by the Cooperative State Research, Education, and Extension Service, U.S. Department of Agriculture, under Agreement No. 2008-33610-19458. Any opinions, findings, conclusions, or recommendations expressed in this publication are those of the authors and do not necessarily reflect the view of the U.S. Department of Agriculture. Lit: S14-01

## environmental data logger

SIE

- 8 analog & 4 digital sensor inputs
- Rugged NEMA 4X fiberglass enclosure
- Cabled & wireless telemetry options
- Internal battery with AC & solar options
- Built-in drivers for environmental sensors

The NexSens **iSIC** (Intelligent Sensor Interface & Control) is the latest in data logging technology. Specifically designed for remote environmental monitoring applications, the **iSIC** offers superior data acquisition performance in extreme conditions. NexSens customers expect reliability, and the **iSIC** data logger delivers unmatched sensor interface and data collection with options for landline phone, cellular, radio, Ethernet, WI-FI, and satellite telemetry. Each **iSIC** data logger simultaneously supports 8 analog inputs & 4 digital inputs for multi-sensor data logging capability.

NexSens iChart Software is a Windows-based program for interfacing both locally (direct-connect) and remotely (through telemetry) to an iSIC data logger or network of data loggers. The iChart Setup Device Wizard includes built-in drivers and a step-by-step interface for setting up and configuring remote monitoring sensors and systems. When connected, the user can quickly configure sample & log intervals, upload data, or troubleshoot communications.

The iSIC data logger arrives ready for long-term deployment. All electronics are housed in a rugged, NEMA 4X enclosure constructed of heavy-duty fiberglass. The built-in 8.5 amp-hour sealed lead acid battery provides 12 volt power to the system, and the battery can be continuously charged using AC or solar power. Polymer-coated circuit boards, sealed connectors, corrosion-resistant stainless steel hardware, and built-in lightning protection ensure reliable performance in the harshest conditions. All sensors are cabled through Sealcon gland fittings to ensure protection from the elements.




## specifications

Analog Inputs	(4) differential or (8) single-ended, additional (4) differential or (8) single-ended		
	optional, 0-2.5 V auto range, 12-bit resolution		
Analog Outputs	(1) 12-bit channel, (1) 12-bit channel optional, 0-5 V or 0-2.5 V programmable		
Power Outputs	(1) 12 V 100 mA configurable switch, (1) 5 V 50 mA analog excitation voltage, (1) 12 output, fused from battery		
Pulse Counters	(1) tipping bucket counter, max rate: 12 Hz		
Digital I/O Ports	(2) standard generic I/O ports		
1-Wire Interface	(1) 1-wire temperature sensor port		
SDI-12 Interface	(1) SDI-12 port		
RS-232 Interface	(3) RS-232 sensor ports, (3) additional optional		
RS-485 Interface	(1) RS-485 port		
Host Interface	(1) RS-232 host port, SDI-12 or RS-485 port can be configured as slave		
Supported Serial Comm Protocols	NMEA 0183 or Modbus RTU		
Internal Memory	2 MB Flash memory, over 500,000 data points minimum		
Power Requirements	Voltage: 5 to 16 VDC		
Typical Current Draw	5 mA sleep, 10 mA processing, 36 mA analog measurement		
Battery	12 V 8.5 A-Hr battery, Internal		
Temperature Range	-20 to +60°C		
Dimensions	NEMA 4X enclosure: 12" x 8.5" x 6.95"		
Compatible Sensors	4-20 mA sensors, 0-2.5 V sensors, SDI-12 sensors, RS-232 sensors, RS-485 sens Modbus RTU sensors, NMEA 0183 sensors, 1-Wire temperature sensors, Thermisto sensors, Tipping bucket rain gauges		









Contents

Part #	Description
ISIC	ISIC data logger
2100-iSIC	iSIC data logger with phone modem telemetry
3100-iSIC	ISIC data logger with cellular modem telemetry
3200-iSIC	iSIC data logger with radio-to-cellular telemetry
4100-iSIC	iSIC data logger with spread spectrum radio telemetry
4200-iSIC	iSIC data logger with radio-to-phone telemetry
5100-iSIC	ISIC data logger with Ethernet connectivity
5200-iSIC	iSIC data logger with radio-to-Ethernet telemetry
5500-iSIC	iSIC data logger with WI-FI connectivity
6100-iSIC	ISIC data logger with Iridium satellite telemetry
1001	iChart Software for Windows-based computers

(4) 56 Ohm resistors for 4-20mA sensor connection

(1) iSIC data logger (1) NEMA 4x enclosure

(1) Grounding lug(2) Gland fittings(1) 8.5 Ahr battery(5) Desiccant packs

MS2 connector for battery charging
 MS8 connector for sensor connection

(1) RS-232 direct-connect cable




937.426.2703 8am to 7pm EST, Monday-Friday


937.426.1125 24 hours a day, every day

> NexSens Technology, Inc. PO Box 151 Alpha, OH 45301-0151

info@nexsens.com

nexsens.com







### YSI 600LS Level Sonde

#### Precise level measurement

The YSI 600LS compact sonde measures level, flow, temperature, and conductivity. The 600LS will seamlessly integrate with the YSI 650MDS, laptop, or data collection platform.



- Easily connects to data collection platforms such as the YSI 6200 DAS
- · Detachable cable lengths
- Compatible with the YSI 650 Multiparameter Display System
- · Temperature/conductivity/vented level
- Optional battery compartment for unattended, internal logging

With the 600LS, tide gauge measurements have never been so easy!

Ideal for use with the YSI 6200 DAS, connecting via SDI-12 for remote and real-time data acquisition applications. Rugged waterproof, the YSI 600LS is perfect for tide gauge monitoring, wetlands level applications, groundwater, estuaries, rivers, and more.

#### **Features**

The YSI 600LS is an economical logging system for long-term, in situ monitoring. It logs at programmable intervals and stores 150,000 readings. The 600LS has extreme level accuracy of  $\pm 0.01$  feet (0.003 m) from 0 to 30 foot depths.



Pure
Data for a
Healthy
Planet.®

Precise Level Measurement
in a Compact Sonde



To order, or for more information, contact YSI Environmental.

+1 937 767 7241 800 897 4151 (US) www.ysi.com

YSI Environmental +1 937 767 7241 Fax +1 937 767 9353 environmental@ysi.com

Endeco/YSI +1 508 748 0366 Fax +1 508 748 2543 systems@ysi.com

SonTek/YSI +1 858 546 8327 Fax +1 858 546 8150 inquiry@sontek.com

YSI Gulf Coast +1 225 753 2650 Fax +1 225 753 8669 environmental@ysi.com

YSI Hydrodata (UK) +44 1462 673 581 Fax +44 1462 673 582 europe@ysi.com

YSI Middle East (Bahrain) +973 1753 6222 Fax +973 1753 6333 halsalem@ysi.com

YSI (Hong Kong) Limited +852 2891 8154 Fax +852 2834 0034 hongkong@ysi.com

YSI (China) Limited +86 10 5203 9675 Fax +86 10 5203 9679 beijing@ysi-china.com

YSI Nanotech (Japan) +81 44 222 0009 Fax +81 44 221 1102 nanotech@ysi.com

ISO 9001 ISO 14001

Yellow Springs, Chio Facility

EcoWatch, Pure Data for a Healthy Planet and Who's Minding the Planet? are registered trademarks of YSI Incorporated. ©2006 YSI Incorporated Printed in USA 1206 E22-01

YSI incorporated Who's Minding the Planet?"

	Range	Resolution	Accuracy
Conductivity*	0 to 100 mS/cm	0.001 to 0.1 mS/cm (range dependent)	±0.5% of reading + 0.001 mS/cm
Salinity	0 to 70 ppt	0.01 ppt	±1% of reading or 0.1 ppt, whichever is greater
Temperature	-5 to +50°C	0.01°C	±0.15°C
Shallow Vented Level	0 to 30 ft, 9.1 m	0.001 ft, 0.001 m	±0.01 ft, 0.003 m

Report outputs of specific conductance (conductivity corrected to 25° C), resistivity, and total dissolved solids are also provided. These values are automatically calculated from conductivity according to algorithms found in Standard Methods for the Examination of Water and Wastewater (ed 1989).

YSI 600LS Sonde Specifications			
Medium	Fresh, sea or polluted water	Software	EcoWatch*
Temperature	-5 to +50°C	Dimensions Diameter length (no batteries) Weight	1.65 in, 4.2 cm 15 in, 38 cm 1.10 lbs, 0.5 kg
Communications	RS-232, SDI-12	Power (optional)	4 AA-size alkaline batteries, or external 12 V DC


Ordering Information		
600LS-10	Temperature, Shallow vented level	
600LS-11	Temperature, Shallow vented level, Battery option	
600LS-12	Temperature, Conductivity, Shallow vented level	
600LS-13	Temperature, Conductivity, Shallow vented level, Battery option	
Cables		
6195	10 ft vented detachable cable	
6191	25 ft vented detachable cable	
6192	50 ft vented detachable cable (Shallow vented level maximum depth is 30 feet.)	

#### **About Conductivity**

The YSI 600LS is available with conductivity and without conductivity. In order to achieve the most accurate level measurements, it is highly recommended you use the 600LS-12 or 600LS-13 with conductivity if your application will require deployments in saline environments. Tidal, estuarine, salt water intrusion in groundwater, and freshwater/saltwater mixing zone studies are typical examples where a higher conductivity reading would require the conductivity sensor to achieve the most accurate, reliable level measurements.

As with all YSI products, there are several accessories available, from calibration solution to carrying cases, to keep your equipment protected and operating well. Please visit www.ysi.com or call 800-897-4151 for more information.











## EcoNet Web-Enabled Datalogger

Delivers data directly via web, email, or FTP

EcoNet is simple to operate, requires the least amount of maintenance of any real-time monitoring system, and makes collaboration easy. Because EcoNet can operate without a base-station computer, data is delivered from the field directly to a secure database web server. This allows limitless scalability—as many as 100 sites can transmit data simultaneously!

Set up is as simple as connecting the battery, antenna, and field cable. EcoNet does the rest—automatically detects the sensors, sets the units and sampling routine, and delivers data. You *do not* have to program code, interpret cryptic data files, join data sets to plot data, nor update software. Plus, you *do not* have to pay for desktop software licenses; only internet access is needed.

You can make changes through a web site from anywhere in the world. You can also rely on YSI's unrivaled technical team should you need advanced support.

#### Collaboration

- Web-based monitoring network is ideal for securely sharing data with strategic partners and co-operators.
- Dedicated public website can display provisional real-time data directly to the public, without the need for local IT resources

#### Integration

- YSI monitoring instrumentation works seamlessly with EcoNet
- Does not require a base station to relay the data
- Does not require a PC in the field to retrieve data and configure system
- · EcoNet web sites can be customized with your logo, colors, and images

#### Information

- Turn data into information by visualizing sites on maps, plots, and gauges
- Tailor reports with information that users are specifically interested in
- · Program alarms for visual display and email notifications
- · Set up automatic emails for daily data reports

#### Services

YSI employs a team of field contractors and engineers who can help survey a site, select the best monitoring locations, install site infrastructure, and coordinate the start-up of your monitoring network. From a single site to hundreds, YSI has tools to get you running with a minimal amount of resources.

For applications <u>not</u> requiring data to the web, YSI EcoLink provides a easy to use interface with data delivery to a desktop computer.



To order, or for more information, contact YSI Integrated Systems & Services

+1 508 748 0366 800 363 3269 (US) systems@ysi.com www.ysi.com

YSI Environmental Yellow Springs, OH +1 937 767 7241 environmental@ysi.com

SonTek/YSI +1 858 546 8327 inquiry@sontek.com

YSI Gulf Coast +1 225 753 2650 gulfcoast@ysi.com

YSI Hydrodata European Support Centre +44 1462 673 581 europe@ysi.com

YSI Middle East (Bahrain) +973 39771055 halsalem@ysi.com

YSI India +91 9891220639 sham@ysi.com

YSI (China) Limited +86 10 5203 9675 beijing@ysi-china.com

YSI Nanotech (Japan) +81 44 222 0009 nanotech@ysi.com

YSI (Hong Kong) Limited +852 2891 8154 hongkong@ysi.com

YSI Australia +61 7 39017223 acorbett@ysi.com

ISO 9001 ISO 14001

(Yellow Springs facility)

YSI EcoNet and Who's Minding the
Planet? are registered trademarks of YSI

Incorporated.

©2009 YSI Incorporated

Printed in USA 0509 E13-03



Y S.1 in corporated Who's Minding the Planet?

#### **EcoNet Features**

#### Data Management Services:

Hardened internet data center Firewall and virus protection Redundant power and connectivity

#### Data Display/Access:

Public web site access with URL View data (tabular or graphical) View historical data Private secure access with password Data display and analysis Download data files (current/historical)

#### Site/Sensor Configuration:

User-selectable sensor/site sample interval User-selectable transmission interval (from a configuration web site)

#### Data Reports:

Fixed time reports (daily, weekly, monthly) User-defined reports

#### Alarm and Alert Set-up:

Create/edit local actions (control)
Create/edit alarm settings and threshholds
Initiate notification on alarm
Event triggers (alarm outputs, sampling rate, transmission rate)

#### Web Site Content Management:

Create and manage content Configure data display Add/edit map images and graphics Create and manage users and roles

#### Data Sharing and Transfer:

FTP data transfer (weekly) Data reports

	Rechargeable gel-cell battery, or lead acid (minimum recommended: 12 V,
	18 Ah)
	Typical current consumption: Normal operation: 55-70 mA
	Sleep mode: 12-15 mA
	16 MB Flash, 32 MB SDRAM
Length	8.75 in. (22.2 cm)
	V New York
105	Alphanumeric LCD, 4 lines x 20 characters Numeric 4 x 4 keypad (0-9, *, #, A-D)
	10 MB on-chip ethernet controller
	10BASE-T port with analog filters
Analog	8 configurable 12 bit analog inputs
	Input voltage: 0 - 2.4 V  Configurable as:
	Single-ended (7 available channels + 1 internal battery monitor) Differential (3 differential pairs)
	4-20 mA loop (7 available channels)
Distal	Programmable gain: 0.5, 1, 2, 4, 8
Digital	8 user-configurable digital I/O (24 channels optional)  Configurable as:
	Input (5 V tolerant)
	Output (max 3 mA)
	Pulse input (accumulation available)
10.15	Digital port output high voltage: 0.8 to 3.1 V Digital port output low voltage: 0.3 to 0.5 V
	Digital port I/O capacitance: 8 pF
47,12	1 RS-232 diagnostic port
	1 SDI-12 serial port, supports up to 10 SDI-12 sensor devices at 1200 bps data rate
	Length Width Height 05

#### automatic weather station



- Measures six weather parameters
- No moving parts
- Solar charged with built-in battery
- Mounts to 2" NPT pipe adapter
- Standalone or cellular telemetry

The WS-100 weather station provides a complete sensor interface and data collection platform for measuring six of the most essential weather parameters. The system simultaneously measures wind speed & direction, liquid precipitation, barometric pressure, temperature, and relative humidity - all in a compact sensor housing with no moving parts. All measurements are based on proven Vaisala technology, such as the WINDCAP sensor for wind speed & direction, the modern RAINCAP sensor for rainfall & rain intensity, and a single module for barometric pressure, temperature, & humidity.

The complete weather station conveniently mounts to the included 2" threaded aluminum mast and is ready for long-term deployment. All electronics are housed in a rugged, NEMA 4X enclosure constructed of heavy-duty fiberglass. The built-in 8.5 amp-hour sealed lead acid battery provides 12 volt power to the system, and the battery is continuously charged via the 20-watt solar power kit. Polymer-coated circuit boards, sealed connectors, corrosion-resistant stainless steel hardware, and built-in lightning protection ensure reliable performance in the harshest conditions.

The WS-100 standalone weather station consists of a NexSens iSIC Data Logger, Vaisala WXT520 multi-parameter weather sensor, 20-watt solar power kit, and a 2" threaded aluminum pole with mounting hardware. The WS-100C real-time cellular telemetry system also incorporates a built-in modem and high gain antenna. The real-time system can be configured for any of the major cellular networks, including Verizon, AT&T, or Sprint Nextel. NexSens iChart Software is a Windows-based program for interfacing both locally (direct-connect) and remotely (through telemetry) to a weather station or network of weather stations.



## specifications

1.5		
Wind Speed Range	0-60 m/s	
Wind Speed Accuracy	$\pm 0.3$ m/s or $\pm 3\%$ at 0 to 35 m/s, whichever is greater; $\pm 5\%$ at 35 to 60 m/s	
Wind Direction Azimuth	0-360°	
Wind Direction Accuracy	±3°	
Precipitation Collecting Area	60 cm <sup>2</sup>	
Rainfall Accuracy	5%	
Pressure Range	600-1100 hPA	
Pressure Accuracy	±0.5 hPA at 0 to 30°C; ±1 hPA at -52 to +60°C	
Humidity Range	0 to 100% RH	
<b>Humidity Accuracy</b>	±3% RH at 0 to 90% RH; ±5% RH at 90 to 100% RH	
Temperature Range	-52 to +60°C	
Temperature Accuracy	±0.3°C (at 20°C)	
Sensor Dimensions	9.4" Height x 4.7" Diameter	
Internal Memory	2 MB Flash memory, over 500,000 data points minimum	
Typical Current Draw	5 mA sleep, 10 mA processing, 36 mA analog measurement	
Battery	12 V 8.5 A-Hr battery, internal	
Additional Sensor Inputs	(8) analog, (3) digital	
Operating Temperature	-20 to +60°C	
Data Logger Dimensions	NEMA 4X enclosure: 12" x 8.5" x 6.95"	
Cellular Modem Power Requirements	350 mA receive/transmit typical, 104 mA idle, power management available	
Cellular Modem Frequency Range	GPRS: Dual band 800/1900 MHz; CDMA: Quad band 850/900/1800/1900 MHz	
Cellular Modem Service Type	GPRS/EDGE/GSM,CDMA	
Supported Cellular Providers	AT&T, Verizon, Sprint, Alltel	







## parts list

Part #	Description	
WS-100	Standalone weather station	
WS-100C	Automatic weather station	
1001	iChart Software for Windows-based computers	
212793	Bird spike kit	
WSP150	Surge protector for Vaisala ultrasonic wind sensors	
A38	Ground kit	
A38-P	Ground kit, pipe attachment	



- 937.426.2703
  8am to 7pm EST, Monday-Friday
- 937.426.1125 24 hours a day, every day

NexSens Technology, Inc. PO Box 151 Alpha, OH 45301-0151

- info@nexsens.com
- nexsens.com

San Joaquin River Exchange Contractors Water Authority	Well Owner	
P.O. Box 2115	AddressCity, State, zip	
Los Banos, CA 93635		
Telephone: (209) 827-8616	Telephone	
Right-of-Entry Agreer For The	nent	
Los Banos Creek Water Resources I	Management Plan	
Los Banos Creek Groundwater and Surface \	Water Monitoring Program	
I,, hereby grant permission to Contractors Water Authority, (Authority) and its officers, empstaff), for ingress and egress with all necessary equipment on Merced, State of California:	the San Joaquin River Exchange ployees, agents (including member district the following lands in the County of	
Assessors Parcel Number	Well Number	
Assessors Parcel Number	Well Number	
Assessors Parcel Number	Well Number	
the following conditions.		
<ol> <li>In the performance of the above-referenced work exercised by the Authority to avoid damage to perhold the Permitter harmless from any such damage Authority or any of the other permittees named by Authority shall not be responsible or liable to Perwhich was beyond the control of the Authority or This permit shall be in full force and effect and shall be in full force and effect and shall be in full force.</li> </ol>	gersons or property. The Authority shall ges caused by the negligence of the herein; provided, however, that the mitter for the consequences of any act the other permittees.  The other permittees as it	
is terminated by either the Authority or the Perm	itter in writing.	
Signatures:		
By:(Well Owner)		
(Well Owner)		
Date:		
Rv.		
By:(Executive Director, San Joaquin River Exchange Con	itractors Water Authority)	
The second section of the section the section of the second section of the secti	and the second s	
Date:		
Date:		