



THE CITY OF SAN DIEGO


DWR's SOUTH COAST REGIONAL FORUM

CITY OF SAN DIEGO'S EXPERIENCE WITH POTABLE REUSE

CATHLEEN C. PIERONI
PRINCIPAL WATER RESOURCES SPECIALIST


SEPTEMBER 30, 2013





WATER REUSE TIMELINE

- 1993 City & County Water Authority propose Water Repurification Project
- 1994-1998 Planning, regulatory reviews & conditional approval, preliminary design on project
- Fall 1998 Water Repurification Project becomes an issue in several closely contested political campaigns
- Spring 1999 Project cancelled by City Council
- 2002-2004 City enters into a settlement agreement with environmental groups committing to:
 - Evaluate improved ocean monitoring
 - Pilot test biological aerated filters
 - Study on increased water reuse



WATER REUSE TIMELINE


- 2004-2005 City undertakes Water Reuse Study
- October 2007 City Council votes to proceed with the Demonstration Project

Water Purification Demonstration Project

- November 2008 City Council approves temporary water rate increase (3.08%) to fund \$11.8 million Demonstration Project
- January 2009 - August 2010

Temporary water rates in effect






PROJECT OBJECTIVES

- Evaluate the feasibility of using advanced treatment technology to produce water that can be sent to San Vicente Reservoir and later distributed as potable water
- Determine if the Demonstration Project provides evidence of viability for a full-scale Indirect Potable Reuse/Reservoir Augmentation (IPR/RA) project






DEMONSTRATION PROJECT COMPONENTS


- Advanced Water Purification (AWP) Facility
- Independent Advisory Panel (IAP)
- San Vicente Reservoir Study
- Regulatory requirements
- Energy and economic analysis
- Pipeline alignment study
- Public outreach & education program





DEMONSTRATION PROJECT COMPONENTS

- Advanced Water Purification (AWP) Facility
- Independent Advisory Panel (IAP)
- San Vicente Reservoir Study
- Regulatory requirements
- Energy and economic analysis
- Pipeline alignment study
- Public outreach & education program





THE CITY OF SAN DIEGO





ADVANCED WATER PURIFICATION FACILITY

City of San Diego's Water Purification Demonstration Project

Purification Process

Demonstration-Scale Project






AWP FACILITY SCOPE OF WORK

- Design, procure, install, operate, and test a one million-gallon per day (mgd) AWP Facility at North City
- Develop and implement a Testing and Monitoring Plan
- Prepare a report based on the operation and testing of the demonstration facility





AWP FACILITY TESTING & MONITORING PLAN


- Testing period August 1, 2011 to July 31, 2012
- Measured for 342 constituents and parameters in recycled water, purified water, and imported water
- Conducted 9,000 individual water quality laboratory tests
- Implemented continuous and daily monitoring before and after each treatment step to verify integrity of each treatment process



AWP FACILITY TESTING & MONITORING PLAN CONCLUSIONS

- Purified water met all federal and state drinking water standards
- Continuous and daily monitoring verified the integrity of the treatment process and equipment
- Lab tests plus continuous monitoring ensures only high quality water is produced
- Water quality comparable to Orange County's Groundwater Replenishment System





AWP FACILITY TESTING & MONITORING PLAN CONCLUSIONS

- Overall water quality was exceptional, comparable to distilled water

Example of water quality results:

	TDS (SALTS)
Purified Water	~15 ppm*
Aqueduct water	~500 ppm
Drinking water	~500 ppm

* *parts per million*



THE CITY OF SAN DIEGO



INDEPENDENT ADVISORY PANEL

INDEPENDENT ADVISORY PANEL (IAP)

- Joseph A. Cotruvo, Ph.D., Joseph Cotruvo Associates
- Richard Gersberg, Ph.D., Occupational & Environmental Health, SDSU
- George Tchobanoglous (Chair), Ph.D., P.E., UC Davis
- James Crook, Ph.D., P.E., Water Reuse
- Audrey D. Levine, Ph.D., P.E., DEE, Drinking Water Research, U.S. EPA
- Sunny Jiang, Ph.D., Civil and Environmental Engineering, UC Irvine
- Michael A. Anderson, Ph.D., Environmental Chemistry, UC Riverside
- Richard J. Bull, Ph.D., Toxicologist, Mobull Consulting
- Michael P. Wehner, Assistant General Manager, OC Water District
- David R. Schubert, Ph.D., Salk Institute for Biological Studies



Listed left to right, by row


INDEPENDENT ADVISORY PANEL

- Convened to provide expert peer review of the technical, scientific, and regulatory aspects of the Demonstration Project
- Similar role as IAP for the City's Water Reuse Study & Orange County's Groundwater Replenishment Project
- Provided feedback regarding
 - San Vicente Reservoir
 - AWP Facility
 - Proposed regulatory framework



INDEPENDENT ADVISORY PANEL CONCLUSIONS

- Ten IAP meetings over three years
- IAP issued summary “letter of findings” November 16, 2012
- Unanimously concluded the Demonstration Project satisfied all City Council directives, and a San Vicente Reservoir augmentation project would be a landmark project




“...The Panel believes that the ... Report ... (is) responsive to the directives set forth by the City Council.”



THE CITY OF SAN DIEGO



SAN VICENTE RESERVOIR STUDY



SAN VICENTE RESERVOIR STUDY

RESERVOIR ENLARGEMENT


- San Vicente Dam and Reservoir constructed in 1944
- Reservoir enlarged from 90,000 acre feet to 247,000 acre feet
- Water Authority is constructing facilities
- City will operate reservoir, dam, and outlet works
- Refilling will take three to five years

1944 to 2012




2013






SAN VICENTE RESERVOIR STUDY

OBJECTIVES

- Understand the characteristics of the enlarged reservoir
 - Establish the retention time and dilution of purified water in the reservoir
- 
- An aerial photograph of the San Vicente Dam and Reservoir. The dam is a long, concrete structure with a central gate. A large yellow crane is visible on the right side of the dam. The reservoir is filled with dark water. The surrounding landscape is hilly and rocky, with some vegetation. A dirt road and some construction equipment are visible on the right side of the dam.
- Determine water quality effects of purified water in the reservoir
 - Secure regulatory approval from CDPH and San Diego Water Board



SAN VICENTE RESERVOIR STUDY

RESULTS

- Reservoir provides an environmental barrier that satisfies anticipated regulatory requirements
- Purified water will be diluted at least 200:1 under all anticipated reservoir operations
- Important aspects of water quality in San Vicente will not be affected by adding purified water
- Reservoir expansion will improve water quality; purified water will not substantially change this



THE CITY OF SAN DIEGO



REGULATORY FRAMEWORK


REGULATORY FRAMEWORK

- Regulatory agencies, CDPH, Regional Water Board, and County Dept of Environmental Health, attended IAP meetings
- Regulators commented on:
 - AWP Facility equipment
 - Testing & Monitoring Plan
 - San Vicente Reservoir Study



CALIFORNIA DEPARTMENT OF PUBLIC HEALTH CONCEPT APPROVAL

- City submitted concept proposal to CDPH in March 2012
- CDPH concept approval letter September 7, 2012



"Based on CDPH's review of the City's ... submittal ... CDPH approves the San Vicente Reservoir Augmentation Concept."


REGIONAL WATER BOARD

- Regional Water Board Resolution re. IPR/RA, October 12, 2011

Regional Water Board "... supports efforts to develop the Reservoir Augmentation Project at San Vicente Reservoir."

- City submitted Proposed Compliance Approach to Regional Water Board on August 30, 2012
- City received a letter of concurrence from the Regional Water Board on February 12, 2013

"The . . . Water Board, with concurrence from USEPA, strongly supports the efforts of the City to develop the San Vicente Reservoir Augmentation Project..."






THE CITY OF SAN DIEGO



ENERGY & ECONOMIC ANALYSIS & FULL-SCALE FACILITIES




DEMONSTRATION PROJECT

SAN VICENTE IPR/RA COST ESTIMATE

	Capital	Annual Operating and Maintenance
AWP Facility	\$144,700,000	\$8,145,000
Pipeline & Pump station	\$224,500,000	\$3,385,000
Increased North City Tertiary Treatment	\$0	\$3,965,000
Total	\$369,200,000	\$15,495,000

- Result - \$2,000 per acre-foot to produce and convey 15 mgd of purified water to San Vicente Reservoir




DEMONSTRATION PROJECT, SAN VICENTE IPR/RA AVOIDED WASTEWATER COSTS

	Capital	Annual Operating and Maintenance
Point Loma Wet Weather Storage Facility	\$123,000,000	\$6,150,000
Reduced Treatment at Point Loma	\$0	\$2,210,000
Reduced Pumping at Pump Station No. 2	\$0	\$450,000
Total	\$123,000,000	\$8,810,000
Total (per-acre-foot basis)	\$1,000	

- Net cost: \$1,000 per acre-foot to produce and convey 15 mgd of purified water to San Vicente Reservoir

PIPELINE ALIGNMENT STUDY

- 22 mile, 36-inch pipeline to convey water from the AWP Facility to San Vicente Reservoir
- Two potential alignments identified:
 - State Route 52 alignment
 - Mission Gorge alignment
- Additional analysis is needed to refine alignment






THE CITY OF SAN DIEGO



PUBLIC OUTREACH & EDUCATION PROGRAM




PUBLIC OUTREACH & EDUCATION PROGRAM

Program Statistics through December 31, 2012

- Speakers Bureau presentations/attendees 132/3,500
- Community events/attendees 42/4,500
- Facility tours/visitors 243/3,244






ON-GOING USE OF REMAINING FUNDS

- Continuing AWP Facility operations
 - Prop 50 extended testing (2013 - 2014)
 - Prop 84 potable reuse study (2014 - 2015)
- AWP Facility tours
- Continuing outreach efforts
 - Tours
 - Speakers Bureau
 - Community events
- Next steps

NEXT STEPS

- Determine appropriate cost-sharing concepts for water-wastewater funding sources
- Determine contracting modes
- Refine pipeline alignment
- Coordinate with Point Loma 2015 Permit Renewal and next steps associated with the Recycled Water Study
- Monitor development of direct potable reuse regulations





THE CITY OF SAN DIEGO





DIRECT POTABLE REUSE CONCEPT

City of San Diego's Water Purification Demonstration Project

Purification Process

Demonstration-Scale Project






SENATE BILL 918

Senate Bill 918 directs CDPH to:

- Adopt regulations for IPR/groundwater replenishment
December 31, 2013
- Convene an expert panel to advise CDPH on
IPR/reservoir augmentation and feasibility of DPR
- Adopt regulations for IPR/reservoir augmentation
December 31, 2016
- Report on feasibility of DPR
December 31, 2016

DIRECT POTABLE REUSE CONCEPT

Without the reservoir, additional barriers (treatment or monitoring) will be required to achieve the same level of public health protection. What are those additional barriers?



multiple treatment barriers are the key to protecting public health

38



Water Purification | Demonstration Project

PureWaterSD.org

Cathleen Pieroni | cpieroni@sandiego.gov | 619.533.6612



Water Purification Demonstration Project



@PureWaterSD



PureWaterSD

